

## Code of Practice for Working in the Road

### Schedule of Special Conditions

Where there are any discrepancies, the following conditions shall take precedence.

#### ***Clause 3.1.4 Road Opening Notice***

For the purposes of clarity, it is noted that excavation includes any method that could potentially disturb the subbase and basecourse of the road and includes but is not limited to directional drilling and tunnelling.

Sub-clause (b) is amended to three working days before work starts.

#### ***Clause 3.2.6.4***

The Kapiti Coast District Council uses the procedures under Transport (Vehicular Traffic Road Closure) Regulations 1965 which requires a minimum of 42 days public notice before a road is closed to traffic.

#### ***Clause 3.2.9***

The principal provider, and any contractor shall hold a current public liability insurance policy to the value of \$1,000,000. This policy shall allow for sufficient cover to mitigate risk, and shall indemnify the road controlling authority against any claims of loss, damage or injury to persons or property that may arise out of, or in consequence of, the construction or maintenance (or lack thereof) of the work. The period of cover shall be for a minimum period of one year from the date of the completion of the works.

The policy shall be extended to cover all insurable risks normally applicable to road work including vibration and removal of support to the value of \$250,000.

#### ***Clause 4.2***

Consideration shall be given to using trenchless technology or rerouting the service to avoid constructing trenches through geotextiles or other stabilised layers or where there are open graded porous asphaltic surfaces because of the difficulty of adequately reinstating these roads.

#### ***Clause 4.7.1.1***

- (c) The Kapiti Coast District Council may waive this requirement for nominated sources of material.

**Clause 4.7.2.3**

Approved methods for reinstating asphaltic concrete (AC) surfaces are:

- (a) chip seal then 30mm of Mix 10 AC
- (b) tack coat then 60mm of Mix 20 AC (light traffic)
- (c)  $\geq$  100mm of Mix 20 AC (heavy traffic).

**Clause 4.7.2.4**

- (f) A specific design is required for reinstatement.

**Clause 4.7.2.12**

Concrete Vehicle Crossings are to be fully replaced to the standard design if they are cut for trenching.

**Clause 4.7.2.6**

Clause 4.7.2.6 is deleted and replaced as follows:

Reinstatement of chip sealed carriageways shall be accomplished using asphalt flush with the existing carriageway surface in accordance with 4.7.2.3 with no overlap onto existing seal. All joints shall be sand sealed.

**Clause 4.8.1**

All road markings shall be reinstated with two coats of fully beaded acrylic paint.

**Clause 5.2**

GAP 150, GAP 100 and GAP 20 are not acceptable backfill materials.

**Appendix L**

Approved methods for reinstating asphaltic concrete surfaces are:

- (a) chip seal then 30mm of Mix 10 AC
- (b) tack coat then 60mm of Mix 20 AC (light traffic)
- (c)  $\geq$  100mm of Mix 20 AC (heavy traffic)

GAP 150, GAP 100 and GAP 20 are not acceptable backfill materials. In situ materials may be accepted provided are compacted to 98% MDD

**Quality Assurance**

The Contractor shall be certified as meeting the requirements of TQS2 for minor works and TQS1 for major or project works.

## **Main Roads**

For the purposes of Preliminary Notification of Working in the Road, the Main Roads are:

- Kapiti Road, Paraparaumu
- Rimu Road, Paraparaumu
- Raumati Road, Raumati
- Marae Lane, Waikanae
- Mill/Main/Tasman Road, Otaki
- Te Moana Road, Waikanae
- Mazengarb Road, Paraparaumu
- Arawhata Road, Paraparaumu
- Te Roto Drive, Paraparaumu
- Poplar Avenue, Raumati
- Ngaio Road, Waikanae

## **Grass Reinstatement**

First class quality topsoil shall be spread and compacted to a depth of 100mm. The topsoil shall be graded evenly from the edge of footpath to the kerb, existing berm, or boundary. The crossfall on the berm shall not be less than 2%. After topsoiling the new berm areas shall be sown with a seed mixture containing 10 parts by weight of Ellet/Nui Rye grass and one part of white clover, or another approved mixture. The mixture shall be sown at a rate of 1 kilogram to 30 square metres area, and the soil top dressed with recommended fertiliser rates before and after planting.

## **Hours of Work**

Hours of work will normally be 7am to 6pm Monday to Saturday except for emergencies.

Lane closures or disruptions are not permitted on the following roads between 7.30am & 9am and 4pm & 5.30pm:

- Kapiti Road, east of Langdale Avenue
- Rimu Road
- Marae Lane
- Raumati Road, east of Matai Road